



KEY:
— Proposed closure
- - - Proposed diversion route

- NOTES:**
1. Traffic management: Road closure - 20:00 to 06:00
 2. All dimensions to be site measured. No scaling is to be carried out from this drawing.
 3. Only the length of road closure, diversion route and diversion signing is shown on this drawing and is offered only as a guide to the number of signs required
 4. The contractor is responsible for signing the diversion route and road closure to the requirements of Traffic Signs Manual - Chapter 8. This shall include roads leading to and from the closed section where required.
 5. Access and access for construction site is to be maintained to businesses and residents as is reasonably practicable.
 6. The contractor will supply signs indicating that "Businesses are open as usual" wherever applicable.

06/07/2018	Final Issue	0	SK
DATE	AMENDMENTS	REV	BY



Engineering Services
 BOROUGH HALL, CAULDWELL ST, BEDFORD, MK42 9AF
 Tel: (01234) 276422

CLIENT
 Environment and Sustainable Communities

SCHEME
 Transporting Bedford 2020
 Manton Lane

DRAWING TITLE
 Diversion Route Plan

GRID REF
 C979.3.0100.04

DRG STATUS
 Information

SCALE @ A2	DATE	DRAWN	CHECKED
NTS	09/07/2018	SK	RB

© Crown copyright and database rights 2018 Ordnance Survey 100049028. You are not permitted to copy, sub-license, distribute or sell any of this data to third parties in any form.